Deloupe Inc
102, rue du Parc Industriel
St-Évariste, QC, G0M1S0
Phone: 418-459-6443 Fax: 418-459-6571

Date	Nbr
30/06/2026	25678

SOLD TO: CA06670

MAXIM TRUCK & TRAILER
580 OAKPOINT HWY
WINNIPEG, MB, R4B0A7
Phone : 1-800-553-7788 Fax :
Contact : CHRIS KOWALIZYN
Cellular : 450-278-5324

DELIVERED TO:

:

DELIVERY	FAB	CARRIER	CUSTOMER ORDER
June 30, 2026	RIMOUSKI	YOUR TRANSPORT	EJ533_120W KICKER

FEDERAL TAX	PROVINCIAL TAX	PAYMENT TERMS	SALES REP.
R104469812	1000709723		OLIVIER LANGIS

QTY ORDERED	PRODUCTS	DESCRIPTION	UOM	UNIT PRICE	TOTAL PRICE
		Type / Dimensions / Structure			
1	EJ553-T001	TILT SEMI-TRAILER OIL FIELD 10' WITH 8 KICK OFF ROLLERS	EA		
		Suspension / axles			
3	26CU25K001	CUSH UNDERSLUNG SUSPENSION 25 000 LBS	EA		
1	30VACK0015	VALVE CONTROLE DE HAUTEUR CUSH ACK-0015	EA		
3	20ESF24032	IMT AXLE F24 ASSY. 25K 0,75 89" 16.5 X 7	EA		
		Tires / Rims / wheels			
12	1523575SOU	TIRE 235/75R17.5 18 PLYS	EA		
12	48AL175SOU	ALUM WHEEL 17.5 X 6.75 5620 LB 8 HOLES	EA		
12	48ES10TR01	ESPACEUR 10 TROUS/22mm	EA		
		Floor			
662	11KE151601	1 5/16" X 7" SHIPLAP KERUING WOOD LUMBER	EA		
-12	11AN280000	ANGELIM PEDRA / BRAZILIAN APITONG WOOD 2" X 8" SKIP DRESSED	EA		
		Coupling / Landing gear /			
1	41TRHYD023	WARRIOR HYDRAULIC WINCH 30K MANUAL WITH 20MM CABLE	EA		
1	41PIKP0805	SAF-HOLLAND REPLACEABLE KINGPIN 2"" X 1/2"" BOLSTER PLATE	EA		
1	33ENLGS316	SET LANDING GEAR MARK V HOLL., 16.5" WITHOUT CROSS SHAFT	EA		
		Brakes and air system			
1	KITA-P105	PNEUMATIC SUSPENSION AND BRAKE KIT 2S/1M SEALCO 3 AXLES (F-F-F) WITHOUT HYDRAULIC JACKS	EA		
3	20WEND0009	AUTOMATIC SLACK ADJUSTER ROCKWELL/MERITOR 28 SPLINES LONG STROKE TYPE 30/30 BRAKE CHAMBER RANGERS	EA		

Deloupe Inc
102, rue du Parc Industriel
St-Évariste, QC, G0M1S0
Phone: 418-459-6443 Fax: 418-459-6571

Date	Nbr
30/06/2026	25678

SOLD TO: CA06670

MAXIM TRUCK & TRAILER
580 OAKPOINT HWY
WINNIPEG, MB, R4B0A7
Phone : 1-800-553-7788 Fax :
Contact : CHRIS KOWALIZYN
Cellular : 450-278-5324

DELIVERED TO:

SAME

DELIVERY	FAB	CARRIER	CUSTOMER ORDER
June 30, 2026	RIMOUSKI	YOUR TRANSPORT	EJ533_120W KICKER

FEDERAL TAX	PROVINCIAL TAX	PAYMENT TERMS	SALES REP.
R104469812	1000709723		OLIVIER LANGIS

QTY ORDERED	PRODUCTS	DESCRIPTION	UOM	UNIT PRICE	TOTAL PRICE
		Electric system			
1	8000060001	7-WAY SOCKET CONNECTION	EA		
1	8000059003	LED TILT HARNESS/LUM GROTE KIT	EA		
1	8000023002	ENS. LIGHT SYSTEM WIDTH EXCESS. (L'OUEST) TILT J/R 2" GROTE	EA		
1	8000092002	REPLACE 2 RED LIGHTS WITH 2 STROBE GROTE IN TILT BUMPER	EA		
		Hydraulic components			
1	KITH-A046	KIT HYD. RACCORDS A AILETTE	EA		
1	KITH-P049	KIT HYDRAULIC TILT CAMEX	EA		
1	8040038001	TILT 3 AXLES TRAILER GREASE KIT	EA		
		Paint and accessories			
1	AUTO-A002	AUTOCOLLANT ET BANDE REFLECHISSANTE TILT OILFIELD	EA		
1	42PO979600	PLASTIC DOCUMENT HOLDER	EA		
		Options			
1	RMOPT-006	PENETRATION DISCOUNT	EA		
1	EJOPT-001	OPTION GREASE SYSTEM 18 POINTS	EA		
1	EJOPT-044	WIDE LOAD KIT (EXTENDIBLE LIGHT, STROBE, WIDELOAD SIGN)(WEST)	EA		
-2	EAOPT-028	ADD 1' OF LENGHT FOR THE DECK	EA		
		Specifications			
001	Lenght :	53' (10'-6 ½'' gooseneck and 43'-5½'' lower deck) FOR TANDEM-DRIVE TRUCK			
002	Width :	120'' overall			
003	Upper frame rail flange :	100,000 p.s.i.			

Deloupe Inc
102, rue du Parc Industriel
St-Évariste, QC, G0M1S0
Phone: 418-459-6443 Fax: 418-459-6571

Date	Nbr
30/06/2026	25678

SOLD TO: CA06670

MAXIM TRUCK & TRAILER
580 OAKPOINT HWY
WINNIPEG, MB, R4B0A7
Phone : 1-800-553-7788 Fax :
Contact : CHRIS KOWALIZYN
Cellular : 450-278-5324

DELIVERED TO:

SAME

DELIVERY	FAB	CARRIER	CUSTOMER ORDER
June 30, 2026	RIMOUSKI	YOUR TRANSPORT	EJ533_120W KICKER

FEDERAL TAX	PROVINCIAL TAX	PAYMENT TERMS	SALES REP.
R104469812	1000709723		OLIVIER LANGIS

QTY ORDERED	PRODUCTS	DESCRIPTION	UOM	UNIT PRICE	TOTAL PRICE
004	Frame rail web :	100,000 p.s.i.			
005	Lower frame rail flange :	100,000 p.s.i.			
006	Type of frame :	DROP ±17.75''			
007	Floor :	Wood 1 5/16" full floor lower deck and upper deck			
008	Floor crossmember :	Steel I-Beam 4" at 20'' c/c and channel 3" at 8'' c/c			
009	Floor covering :	Same paint as the structure (see note 3), wood coated with oil			
010	Side rails :	100,000 p.s.i. "H" shaped for gooseneck and "J" for bed			
015	Rear bumper :	(HSS) 4" x 4" x 3/16" welded on sliding boogie			
018	Bolster plate :	1/2" 100,000 p.s.i. inged with spring lock			
020	Coupling device :	Bolted king pin at 13"			
021	Fifth wheel height :	50"			
025	Axles spacing :	Tridem a 60", hydraulic sliding			
046	Document holder :	Included, plastic			
047	Revolving lamp/strobe :	(1) OVAL STROBE LIGHT ON EACH SIDE INCLUDED IN THE REAR LIGHT SYSTEM			
048	Flags :	N/A			
049	Wide load panel :	INCLUDED ALUMINIUM			
050	Light extension :	(4) SWING OUT OVER WIDTH LOAD LIGHT 2" NO FLASHING, SYSTEM FOR TILT			
051	Tool box :	(3) included 0ne driver side and two passenger side			
053	Spare wheel carrier :	None			
054	Conspicuity tape :	Included			
056	Mud flap :	(1) Set at the back + (1) set in front of dolly + (1) Rubber carpet in front tower			
060	Paint :	Black			
061	Primer :	Epoxy			
084	Strap tie-down :	(10) Pockets for lowboy, helper side - (10) Pockets for lowboy, driver side			

Deloupe Inc
102, rue du Parc Industriel
St-Évariste, QC, G0M1S0
Phone: 418-459-6443 Fax: 418-459-6571

Date	Nbr
30/06/2026	25678

SOLD TO: CA06670

MAXIM TRUCK & TRAILER
580 OAKPOINT HWY
WINNIPEG, MB, R4B0A7
Phone : 1-800-553-7788 Fax :
Contact : CHRIS KOWALIZYN
Cellular : 450-278-5324

DELIVERED TO:

SAME

DELIVERY	FAB	CARRIER	CUSTOMER ORDER
June 30, 2026	RIMOUSKI	YOUR TRANSPORT	EJ533_120W KICKER

FEDERAL TAX	PROVINCIAL TAX	PAYMENT TERMS	SALES REP.
R104469812	1000709723		OLIVIER LANGIS

QTY ORDERED	PRODUCTS	DESCRIPTION	UOM	UNIT PRICE	TOTAL PRICE
085	Tie-down rings :	Key holes on both side rails + one rail in the center full length of the platform at 24" c/c			
088	Hydraulic couplers :	1''-NPT Wings type with plug			
089	Hydraulic cylinder A :	(2) Hydraulic cylinder 6" bore - 30" stroke for tilt			
090	Hydraulic cylinder B :	(1) Hydraulic cylinder 6" bore - 190" stroke for sliding boogie.			
093	Hydraulic control valve :	Control Valve 3 taps			
094	Hydraulic winches :	Included 30,000 LBS with 20mm×100' steel cable with hook with wireless remote control			
095	Wireless remote control :	(1) Included for winch			
097	Stationary engine :	Not Included			
104	Chain stop :	(3) Chain stop fabricated			
105	Winches :	(6)Standard 3 bars #48101-10, without handle, helper side			
106	Winches :	(6)Standard 3 bars #48101-10, without handle, driver side			
	---------- :	----------			
	Remark 1 :	Included attachments for flip neck extension (flip not included)			
	Remark 2 :	Cylinder with closed rod during transportation			
	Remark 3 :	Sand on paint on gooseneck and rear end			
	Remark 5 :	45T over 10' or 55T overall			
	Remark 6 :	Chaqun des (8) rouleaux hydraulique viens avec (4) trous de goujons			
	Remark 7 :	(2) OVALES RED LIGHTS + (1) OVALES STROBE LIGHTS, EACH SIDE ON REAR BUMPER			
	Remark 8 :	(2) Ovales red Lights + (1) Ovales strobe Lights, each side on rear bumper			
	Remark 10 :	ATTENTION This trailer is equiped with TIRE SIZE 235/75R17.5			
	Remark 12 :	INCLUDES (18) GREASE POINTS WITH ALLOMETER IN THE REAR BUMPER			

Deloupe Inc
102, rue du Parc Industriel
St-Évariste, QC, G0M1S0
Phone: 418-459-6443 Fax: 418-459-6571

Date	Nbr
30/06/2026	25678

SOLD TO: CA06670

MAXIM TRUCK & TRAILER
580 OAKPOINT HWY
WINNIPEG, MB, R4B0A7
Phone : 1-800-553-7788 Fax :
Contact : CHRIS KOWALIZYN
Cellular : 450-278-5324

DELIVERED TO:

SAME

DELIVERY	FAB	CARRIER	CUSTOMER ORDER
June 30, 2026	RIMOUSKI	YOUR TRANSPORT	EJ533_120W KICKER

FEDERAL TAX	PROVINCIAL TAX	PAYMENT TERMS	SALES REP.
R104469812	1000709723		OLIVIER LANGIS

QTY ORDERED	PRODUCTS	DESCRIPTION	UOM	UNIT PRICE	TOTAL PRICE
	Remark 16 :	Ride height valve on last axle			
	---------- :	----------			
176	Trailer weight :	±2% 13 000 kg			

This quote is valid for a period of 30 days following the date of issue of this document. The delivery date is for information only; a delivery date will be confirmed upon confirmation of the order.

A 10% deposit is required to order.
A balance of 90% has to be paid before delivery.

Thank you for your collaboration.

SPEC CHANGES WITHIN EIGHT (8) WEEKS OF PRODUCTION DATE MAY RESULT IN DELAYS IN THE DELIVERY DATE AND EXTRA CHARGES WILL BE APPLY.

Accepted by: _____
Printed name

_____ _____
Date Signature

Your order #:

Signature: _____