# QUOTATION/CONTRACT (DEALER PRICE)



*Unit may differ then the picture shown*

## 2025 Trout River Live Bottom Trailer SC-37'-3

Prepared for:

Date:

SW134703

### Standard Features

Hardox AR450 rounded tub for increased volume and lower center of gravity (trailer is 10' high)
Long life urethane paint with rust inhibiting primer / aluminum sheeting & insulated tub
Conveyor control valve forward/ reversing with auto-belt feature
Bolted 80 KSI formed C channel cross bars for easy replacement
Uniroyal HS2 11R22.5 tires on Accuride enhanced polished rims
Tub is huck bolted to suspension for less wear and stress
Eye level 180 degree strobe light
Cramaro electric end to end semi-waterproof tarp
Air operated mud flaps
Ground level lockout & platinum addition tailgate

### Additional Options (Prices Subject to Change)

| | | | |
|---|---|---|---|
| ☐ | Compression locks | ☐ | Asphalt chute attachment |
| ☐ | Hydraulic knife gate /comp. locks | ☐ | Alum. grain chute attachment |
| ☐ | Tool box (14"x12"x24") | ☐ | Bottom row lighting |
| ☐ | Dial flow control | ☐ | 6X flush mount strobe lights |
| ☑ | LED Work lights | ☐ | Polished aluminum panels |
| ☑ | Release agent tank | ☐ | Polished stainless steel panels |
| ☐ | Wireless remote | ☐ | 3/8" Aggregate liner |
| ☐ | Front walk through door | ☐ | Disc brakes |
| ☐ | Air weigh scale | ☐ | Tiremax auto inflation |
| ☐ | 2X 10ft hydraulic hose extensions | ☐ | Stainless steel fenders |

### Tarp Options

| | |
|---|---|
| ☐ | Elcargo 521 electric sideroll tarp |
| ☐ | Elcargo 421 manual sideroll tarp |
| ☐ | Electric mentor tarp |
| ☐ | End to end mesh tarp |

| Elcargo 521 electric sideroll tarp | | Elcargo 421 manual sideroll tarp | |
|---|---|---|---|
| ☐ | Fix on curb side | ☐ | Fix on curb side |
| ☐ | Fix on driver side | ☐ | Fix on driver side |

### Custom Color Options

****Custom color will be quoted once paint code is received****

| | |
|---|---|
| Tub color(Default black): | |
| Bogey color(Default black): | |
| ☐ Custom Paint | $ - |

**Notes:**

### Pricing CAD

| | | | |
|---|---|---|---|
| Base Price: (EXW Coleman, PE) | | Subtotal: | |
| Cost of Options: | | Quantity: | |
| Shipping: ***NOT INCLUDED*** | | **Trout River Final Sales Price:** | |

### Terms & Conditions

Applicable taxes & shipping are extra. 20% Deposit required prior to production. Full payment due 30 days after invoice is received Unit to be paid in full prior to shipment. Prices may be subject to adjustment in light of global material shortages and increased raw material costs. Trout River will advise customers of any adjustments before production commences.

We the undersigned accept these terms and enter into the contract for the construction/purchase of this unit.

Customer Signature Date